

PERFORMANCE RESULTS

Kingspan Environmental Limited
College Road North, Aston Clinton, Buckinghamshire, HP22 5EW
United Kingdom

EN 12566-1
Part 1: Prefabricated septic tanks
Results corresponding to the Irish National Annex for IS EN 12566-1
Test reports PIA2015-1503-1018

GAMMA Septic Tank

Material	Polyethylene
Crushing resistance (pit test)	pass (for wet ground conditions also)
Watertightness	pass
Nominal capacity (total usable volume)	Single Stage: 2 m ³ (2,843 l), 4 m ³ (4,010 l) Twin Stage: 2 m ³ (2,829 l) 4 m ³ (4,010 l)
Hydraulic efficiency	99.81 % (Single Stage 2800) 99.97 % (Twin Stage 2800)

Performance tested by:

PIA – Prüfinstitut für Abwassertechnik GmbH
(PIA GmbH)
Hergenrather Weg 30
52074 Aachen, Germany

This document replaces neither the declaration of performance nor the CE marking.



Notified Body
No.: 1739



Certified according to
ISO 9001:2008



Prüfinstitut für Abwassertechnik GmbH
[Signature]
Geprüft - tested - testé

Elmar Lancé

July 2015